



SUPPLY & INSTALL 2ND. STEEL BEAMS TO SENG SPEC. INCLUDE 60 MIN. INTUMESCENT PAINT

CAFE FLOOR AREA - APPROX. 70m²
REMOVE EXISTING SUB-FLOOR, SUPPLY & INSTALL CONCRETE FLOOR TO MATCH LEVEL OF EXISTING FLOOR.

ALLOW FOR REPAIR WORK TO MASONRY WALLS INCLUDING PREPARATION TO RECEIVE SKIM FINISH

CONSTRUCT FULL HEIGHT CUPBOARD FOR ELECTRICAL BOARD

DOOR PACK TO BE FITTED IN ACCESSIBLE BATHROOM

HALF-HEIGHT WALL TO COVER PLUMBING (900H)

- KEY**
- Full-Height Wall
 - Half-Height Wall

NOTES

Please do not scale from this drawing.

Drawing represents a non-technical summary of design intent.

Contractor to verify dimensions on site.

It is the contractor's responsibility to check all information contained in this drawing. Seek clarification if in doubt.

// PROJECT PROPS SHOP
 // DWG TITLE GENERAL ARRANGEMENT
 // DWG NO 401 - B
 // SCALE 1:50 @ A2
 // DATE 06/06/2023
 // ISSUE CONSTRUCTION
 // DRAWN BY
 // WALKER



SHAPE STUDIO
 0117 429 0170
 SHAPESTUDIO.CO.UK

THE OLD SORTING OFFICE
 EASTFIELD ROAD
 BRISTOL BS5 6AB